# **Public Information Meeting**

State Project No. 102-295
Median Reconstruction and
Resurfacing of I-95
from
Exit 16 in Norwalk
to
Exit 17 in Westport

January 7, 2016 - Norwalk

January 13, 2016 - Westport

### **Agenda**

Introduction Andy Fesenmeyer – CTDOT

Design Presentation

Jeffrey Keefe – AECOM

Don Costello – AECOM

Rights of Way Process

Michelle Miller – CTDOT

Questions & Comments
Andy Fesenmeyer - CTDOT



# **Project Purpose**

- Improve Driver Safety
  - 12 foot wide inside shoulder
  - New higher and stronger concrete barrier in median
- Repave the Existing Roadway
- Bridge Reconstruction

#### **Project Funding**


- Federal Highway Administration 90%
- State of Connecticut 10%
- Local Yankee Doodle Trail

#### **Project Schedule and Cost**

- Current Status Design is 50% complete
- Final Design Summer 2017
- Advertise for Construction Bids End of 2017
- Start Construction Spring 2018
- Finish Construction Fall 2019

Total Estimated Construction Cost: \$55 to \$70 Million

### **Project Location**



### **Project Elements**

- Reconstruct Median
- Mill and Overlay existing I-95
- Drainage Improvements
- Park and Ride Commuter Lot
- Segment of the Yankee Doodle Trail
- Maintain Traffic During Construction
- Utility Relocation
- Regulatory Permits
- Rights-of-Way
- Bridge Reconstruction



# **Existing I-95 Roadway**



# **Proposed I-95 Roadway**



# <u>Drainage Improvements, Yankee</u> <u>Doodle Trail and Park & Ride Expansion</u> <u>at Hendricks Avenue</u>




# Maintaining Traffic During Construction


Provide 3 Lanes on I-95 except for occasional weekend and off peak traffic periods for:

- Mill and pave operations
- Bridge reconstruction


### **Maintenance of Traffic I-95**



STAGE 1
OUTSIDE SHOULDER RECONSTRUCTION
3 TRAVEL LANES



STAGE 3 MEDIAN RECONSTRUCTION 3 TRAVEL LANES



STAGE 2 — MILL AND OVERLAY EXISTING PAVEMENT DURING OFF PEAK HOURS

3 TRAVEL LANES DURING PEAK HOURS



STAGE 4 - CONSTRUCT 2" OVERLAY
3 TRAVEL LANES DURING PEAK HOURS

STAGE 5
INSTALL FINAL COURSE
3 TRAVEL LANES DURING PEAK HOURS



### **Utility Relocation**

Strawberry Hill Avenue Bridge
Water main
Overhead wires and pole
Gas main
Electric duct

Saugatuck Avenue Bridge
Overhead wires

CTDOT is currently coordinating with the appropriate utility owners.



### **Regulatory Permits**

# CT Dept. of Energy and Environmental Protection

- Flood Management Certification
- Office of L.I. Sound Programs
- Inland Wetlands
- Stormwater Discharge General

#### **Army Corps of Engineers**

Category 1 General Permit



### **Noise Barriers**

Project criteria - CTDOT Noise Abatement Policy & Federal Register 23 CFR Part 772 Criteria requirements:

- Highway on a new location
- Horizontal or vertical alignment is altered
- Additional lanes are proposed
- New facilities are proposed such as a toll plaza, weigh station or rest area

This project does not meet the above criteria

# **Rights-of-Way**

# **Anticipated Impacts:**

- Slope Easements
- Construction Easements

# **Bridge Reconstruction Strawberry Hill Ave. over I-95**

#### What are we doing?:

- Replace Bridge Deck and Girders (Superstructure)
- Raise the Superstructure to Improve Vertical Under Clearance
- Temporary Pedestrian Bridge over I-95
- Maintain 2-Lanes on Strawberry Hill Ave.



What are we doing?

- Replace Bridge Deck and Girders
- Minor Widening
- Evaluating:

Conventional Construction Methods vs.

**Accelerated Construction Methods** 



#### **Conventional Construction Methods:**


- Eight Construction Stages
- Maintains All Lanes Narrowed for Construction
- Duration Approximately 2 Years




#### **Accelerated Construction Methods:**

- Get In / Get Out / Stay Out
- Replace Portion of Structure over a Weekend
- Maintain at Least 2 Lanes Each Direction
- Four Weekends to Replace Superstructure
- Duration Approximately Six Months
- Public Outreach







Stage 1



Stage 2




Stage 3



Stage 4


# <u>Detour - Saugatuck Avenue</u>





#### Exit 17 Ramp Detour

I-95 NB On-Ramp
I-95 SB Off-Ramp





# Bridge Reconstruction I-95 over Saugatuck River

#### What are we doing?:


- Expansion Joint Replacement
- Evaluating:

Conventional Construction Methods vs.

**Accelerated Construction Methods** 



# Bridge Reconstruction I-95 over Saugatuck River



#### **Accelerated Construction Staging**

# **Public Outreach**

#### **Public Media**

- Project Website
- Press Notices
- Detour Signing
- Live Camera Feeds
- Message Boards

#### **I-95 Intelligent Transportation System**

- Cameras
- Message Boards
- Advisory Radio
- Travel Alert Systems CT, NY, NJ, MA, RI



# Department of Transportation Division of Rights of Way (ROW)

Michelle Miller
Project Coordinator
2800 Berlin Turnpike
P.O. Box 317546
Newington, CT 06131-7546



### **Function**

• Acquire all property/property rights necessary for transportation projects.



### **Statutory References**

• State of Connecticut

C.G.S. Sections 13a-73 & 13a-98e

• Federal

Uniform Relocation Assistance and Real Properties Acquisition Act of 1970, as amended.

### **Types of Property Impacts**

- Total Acquisitions
- Partial Acquisitions
- Easements
- Construction Easements
- Rights




\* Note: Specific impacts are subject to change as the design progresses.



### **ROW Acquisition Process**

- Letter of Intent to Acquire
- Valuation
- Offer of Just Compensation
- Negotiation
- Acquisition
  - Agreement
  - Eminent Domain/Condemnation
    - » 6 month appeal period





# **Timing for Acquisitions**

- All property rights must be acquired by the project advertising date.
- Current Advertising Date:
   December 2017

### **Contact Information:**

Mr. Andy Fesenmeyer
Project Manager - Highway Design
Connecticut Department of Transportation
2800 Berlin Turnpike
P.O. Box 317546
Newington, CT 06131-7546

E-Mail: andy.fesenmeyer@ct.gov

**Comment Period Ends January 31, 2016** 

THANK YOU...

