

TOWN OF WESTPORT REQUIRED INSPECTIONS

The site set of plans approved by the Building Department must be kept on the job site at all times and made available to the inspector.

Footing Inspection Prior to pouring concrete. All forms and reinforcing steel must be in place.

Foundation Wall Reinforcing Inspection Prior to pouring concrete. All forms and reinforcing steel must be in place.

<u>Back-Fill Inspection</u> After foundation is parged and waterproofed, footing drains (if required) must be installed. <u>Note:</u> Foundation walls must be sufficiently braced to prevent damage by the backfill.

Sheathing and Strapping Inspection Inspection for braced walls and strapping prior to installing air infiltration barrier and siding.

Rough-All-Trades All rough framing, electrical, plumbing, heating, and air conditioning must be complete, stairs (temporary or permanent) must be installed, and structure must be completely <u>weathertight</u>. <u>Note</u>: This inspection will not be scheduled by the Building Department unless all sub-contractor permits have been issued.

<u>Insulation Inspection</u> Prior to installing drywall. <u>Note</u>: Jobsite must be broom clean and insulation dust must settle/vapors must dissipate at least 24 hours prior to inspection for safe air quality.

<u>Service Inspection</u> Electrical Service Inspection. <u>Note</u>: Plastic meter socket cover must be installed. Ground rods or Ufer ground shall be visible or clearly marked. Trenches shall be inspected at the time of the service inspection. All other electrical trenches shall be inspected prior to backfilling.

<u>Fireplace Inspections</u> <u>Note</u>: A Masonry Fireplace Permit is required.

- Hearth extension inspection reinforcing steel must be installed.
- Throat inspection at installation of first flue tile.

<u>Gas piping inspection</u> All gas piping must be completely installed and properly fastened, supported and nail plated. All required shut-off valves must be installed at each appliance location. A pressure test is required - the system shall be pressurized to a minimum of 15 PSI on a 30# gauge. A tag shall be displayed at the gauge with the time, date and the set pressure. Exterior tanks shall be inspected prior to backfill - cathodic protection shall be installed and suitable backfill shall be stockpiled at the site.

Swimming Pool Note: A temporary enclosure must be erected and maintained until the permanent barrier is installed.

- Reinforcing steel and electrical bonding inspection.
- Final inspection (includes fencing and gate to code.)
- Deck reinforcement and/or perimeter surface bonding inspection.

<u>Commercial Fire Alarm Inspection</u> All devices must be installed, uncovered, operational, and labeled to match FACP programming. You must provide: Zone listing, Wiring Diagram, Operations Manual, NFPA-72 Completion Form. Site testing of all devices for visibility, audibility, correct zone report at FACP, fire drill, silence and system reset, and timely relay of fire signal by monitoring station to WFD.

<u>Certificate of Occupancy</u> Final inspection prior to issuance of a Certificate of Use and Occupancy (required before actual occupancy.) <u>Note</u>: Make sure smoke and carbon monoxide detectors are installed to code. Also submit results of the required blower door test (for new residential construction) prior to the final inspection.

Inspection results will be emailed to you. If you do not receive an email within 24 hours, visit the Building Departments Web Site or call the Building Department at 203-341-5025 for results.

Note: Except in cases of emergency, construction or repair work that is accompanied by noise shall be prohibited within the Town of Westport between the hours of 8:00 p.m. and 7:00 a.m. on weekdays and 9:00 a.m. on Saturday, Sunday and legal holidays.

Rev. 10/1/2022