

Vicinity Map  
Scale: 1" = 500'




COVERAGE INCLUSIONS (EXISTING):	
BUILDING = 1,133 SF	
FRONT COVERED PORCH = 45 SF	
GREENHOUSE = 47 SF	
DECK/STEPS = 273 SF	
DRIVEWAY = 1,827 SF	
PLAY AREA PLATFORM = 24 SF	
TOTAL BUILDING AREA = 1,522 SF	
TOTAL COVERAGE AREA = 3,349 SF	
COVERAGE INCLUSIONS (PROPOSED):	
BUILDING = 1,661 SF	
FRONT COVERED PORCH = 45 SF	
REAR BALCONY = 111 SF	
DRIVEWAY = 2,511 SF	
PLAY AREA PLATFORM = 24 SF	
TOTAL BUILDING AREA = 1,841 SF	
TOTAL COVERAGE AREA = 4,352 SF	

AVERAGE GRADE	
73.0	NW Cor
68.0	NE Cor
72.9	NE Cor
70.4	E Face
67.2	SE Cor
66.2	S Face
65.3	SW Cor
65.7	W Face
= 548.7 / 8 = 68.6	
91.2	(Roof Midpoint)
68.6	(Average Grade)
22.6	(Height) 35' Max.

BASE LOT CALCULATION ZONE A (All entries in square feet-- do not write in shaded areas)		EXISTING CONDITIONS VS. (ALLOWED)	PROPOSED CONDITIONS
1.	GROSS LOT AREA	= 11,351 SF (21,780)	= 11,351 SF (21,780)
2.	Above Ground Utility Easements	0 +	
3.	Streets and Roads	0 +	
4.	Other Exclusive Surface Easements	0 +	
5.	TOTAL EASEMENTS AND ROADS (Sum of lines 2,3 and 4)	= 0	= 0
6.	Wetlands area	0 +	
7.	Steep Slopes of 25% or greater	0 +	
8.	TOTAL WETLAND AND STEEP SLOPES (Sum of line 6 & 7)	= 0	
9.	Wetlands/Slopes reduction 0.8 x line 8	= 0	= 0
10.	BASE LOT AREA Lines 1, minus line 5 and line 9	= 11,351 SF	= 11,351 SF
MAXIMUM LOT AREA COVERAGE CALCULATION			
11.	BASE LOT AREA (Copied from line 10, above)	11,351 SF	
12.	Square feet of Total Coverage	3,349 SF	4,352 SF
13.	Line 12 divided by line 11 for a percentage	29.5% (25%)	38.3% (25%)
14.	Square feet of Building Coverage	1,522 SF	1,841 SF
15.	Line 14 divided by line 11 for a percentage	13.4% (15%)	16.2% (15%)

IF LINE 13 AND 15 ARE EQUAL TO OR LESS THAN THE PERCENTAGE FOR MAXIMUM PERMITTED BUILDING AND/OR TOTAL COVERAGE WITHIN THE ZONING DISTRICT, THE COVERAGE COMPLIES



**NOTES:**

- This survey and map has been prepared in accordance with the Sections 20-300b-1 through 20-300b-20 of the Regulations of Connecticut State Agencies - "Minimum Standards for Survey and Maps in the State of Connecticut" as endorsed by the Connecticut Association of Land Surveyors, Inc., August 29, 2019. It is a Zoning Location Survey based upon a Resurvey and conforms to Horizontal Accuracy Class A-2 and Topographical Class T-2.
  - Distances shown ± from buildings to property lines are for reference purposes only and are not to be used to establish boundaries.
  - Zoning information shown on this map must be reviewed and confirmed by the appropriate Town of Weston authorities prior to use.
  - Property is served by public water and sanitary sewer.
  - Unauthorized alterations or additions to this survey, which bears the surveyor's embossed seal, renders any declaration shown hereon null and void.
  - The property is located in Zone X per FEMA Flood Map #09001C0414G; Panel 414 of 626; Effective Date: 7/8/2013.
  - Reference is hereby made to Connecticut General Statute 8-13a, as amended, with regards to existing structures three or more years old.
  - The topography shown hereon is the result of a field survey. The elevations have been adjusted to coincide with the Town of Westport GIS system.
  - It is the owner's and/or contractor's responsibility to obtain any and all required permits and/or variances that may be required prior to any construction activity.
  - This lot is non-conforming due to lot size; the building setbacks are as follows: Front Setback = 30'; Rear Setback = 25'; Side Setback = 10'
- Reference is made to the following documents:
  - RM 9307 - "Map Showing Sanitary Sewer Easement; To be Conveyed to Van & Rachael Wallach; 25 Hickory Drive; to Town of Westport; Scale: 1" = -20'; Feb. 10, 1993; by Walter H. Skidd."
  - RM 2630 - "Property of Sereno Jennings; Westport, Conn.; scale: 1" = 40'; Jan. 1950; by Charles S. Lyman."
  - RM 8026 - "Map of Property; Prepared for; The Jennings Realty Co.; Westport, Conn.; Scale: 1" = 20'; Feb. 26, 1974; by Leonard Surveyors."
  - RM 9306 - "Map Showing Sanitary Sewer Easement; To be Conveyed to Arthur S. & Francine R. Crystal; 27 Hickory Drive; to Town of Westport; Scale: 1" = -20'; Feb. 10, 1993; by Walter H. Skidd."
  - Volume 45 Page 478 (CLP Easement); Volume 100 Page 198 (BHC Easement); Volume 100 Page 215 (CLP Easement); Volume 110 Page 98 (Water Easement & Agreement); Volume 118 Page 449 (Water & Drainage Easement); Volume 1313 Page 203 (Sewer Easement);
- The underground utilities shown, if any, have been located from visible field survey information. No attempt has been made as a part of this survey to obtain or show data concerning existence, size, depth, condition, capacity, or location of any utilities or municipal/public service facilities. The surveyor makes no guarantees that the underground utilities shown comprise all such utilities in the area either in service or abandoned. For information regarding these utilities or facilities, please contact the appropriate agencies. Call Before You Dig, Inc. (1-800-922-4455).

**LEGEND**

- HYDRANT
- MANHOLE
- ⊕ GAS VALVE
- ⊕ UTILITY POLE
- ⊕ WATER VALVE
- ⊕ LAMP POST
- CATCH BASIN
- ⊕ ELECTRIC BOX
- ⊕ SIGN
- ⊕ MAILBOX
- DECIDUOUS TREE
- CONIFEROUS TREE
- ⊕ TEST HOLE
- EXISTING IRON PIN
- EXISTING CONCRETE MONUMENT
- ⊕ STONE BOUND
- ⊕ HEDGE
- ⊕ STONEWALL
- WL — INLAND WETLANDS
- — METAL FENCE
- — WOOD FENCE
- — EXISTING CONTOUR LINE
- × 132.0 EXISTING SPOT ELEVATION

NOT VALID UNLESS EMBOSSED WITH SEAL OR FIXED WITH THE LIVE STAMP OF THE SIGNATORY  
TO MY KNOWLEDGE AND BELIEF, THIS MAP IS SUBSTANTIALLY CORRECT AS NOTED HEREON



Michael S. Shevlin, Jr. PLS #70339

ALL WORK, LABOR, AND MATERIALS TO BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES AND LAWS WHICH SHALL TAKE PRECEDENCE OVER THESE DRAWINGS IN THE EVENT OF ERRORS AND/OR OMISSIONS HEREIN.  
THE WORD "CERTIFY" OR "DECLARE" IS UNDERSTOOD TO BE AN EXPRESSION OF PROFESSIONAL OPINION BY THE LAND SURVEYOR AND/OR ENGINEER, WHICH IS BASED ON THEIR BEST KNOWLEDGE, INFORMATION AND BELIEF, AS SUCH IT CONSTITUTES NEITHER A GUARANTEE OR WARRANTY.  
THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY AND CONFIDENTIAL PROPERTY OF SHEVLIN LAND SURVEYING, LLC. REPRODUCTIONS, PUBLICATION, DISTRIBUTION, OR DUPLICATION IN WHOLE OR IN PART REQUIRES THE WRITTEN PERMISSION OF SHEVLIN LAND SURVEYING, LLC. THIS DOCUMENT AND COPIES THEREOF ARE VALID ONLY IF THEY BEAR THE LIVE SIGNATURE AND LIVE SEAL OF THE DESIGNATED LICENSED PROFESSIONAL.  
© COPYRIGHT 2024. ALL RIGHTS RESERVED

**ZONING LOCATION SURVEY**  
**DEPICTING PROPOSED CONDITIONS**  
PREPARED FOR  
**LOUIS E. DONOFRIO JR. & TAMMY W. LO**  
**#25 HICKORY DRIVE**  
**WESTPORT, CONNECTICUT**



NO.	DATE	DESCRIPTION	DATE:	SCALE:	DRAFTER:	JOB NUMBER:	SHEET NUMBER:
2	8-20-2024	TOWN COMMENTS	4-1-2024	1" = 20'	DCH	11722	1/1
1	6-11-2024	PROPOSED FEATURES					
REVISIONS							

**SHEVLIN LAND SURVEYING, LLC**  
593 Main Street, Monroe, CT - 303 Linwood Avenue, Fairfield, CT  
(203)-218-5840 - ShevlinLS.com