# SILT FENCE WILL BE INSTALLED ALONG THE TOE OF ALL CRITICAL CUT AND FILL

LAND DISTURBANCE WILL BE KEPT TO A MINIMUM; RESTABILIZATION WILL BE SCHEDULED AS SOON AS POSSIBLE.

SLOPES, SOIL STOCKPILE AREAS, AND IN THOSE AREAS SHOWN ON THE PLAN. ALL EROSION AND SEDIMENT CONTROL MEASURES WILL BE CONSTRUCTED IN ACCORDANCE WITH THE STANDARDS AND SPECIFICATIONS OF THE STATE OF

GENERAL EROSION AND SEDIMENT CONTROL NOTES

- CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL, 2002. EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED PRIOR TO LAND DISTURBANCE WHENEVER POSSIBLE.
- ALL TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE PROPERLY MAINTAINED UNTIL STABILIZATION HAS BEEN ACHIEVED.
- ADDITIONAL CONTROL MEASURES WILL BE INSTALLED DURING THE CONSTRUCTION PERIOD IF NECESSARY OR REQUIRED. A MINIMUM OF 50 FEET OF SILT FENCE SHALL BE STORED AT THE SITE FOR EMERGENCY USE.
- ANY EXCAVATIONS THAT MUST BE DEWATERED WILL BE PUMPED INTO A 15'x15' DIRTBAG ON-SITE. THE INLETS OF ALL PUMPS ARE TO BE FLOATED A MINIMUM OF 24 INCHES OFF THE BOTTOM OF THE EXCAVATION, THE CONTRACTOR SHALL KEEP A MINIMUM OF (2) 15'x15'

DIRTBAGS ON-SITE THROUGHOUT THE EXCAVATION OF PROPOSED FOUNDATIONS.

- WATER AND CALCIUM CHLORIDE SHALL BE APPLIED TO UNPAVED ACCESSWAYS TO PREVENT WIND GENERATED SEDIMENTS AND DUST.
- DEBRIS AND OTHER WASTES RESULTING FROM EQUIPMENT MAINTENANCE AND CONSTRUCTION ACTIVITIES WILL NOT BE DISCARDED ON-SITE.
- SEDIMENT REMOVED FROM CONTROL STRUCTURES WILL BE DISPOSED OF IN A

MANNER WHICH IS CONSISTENT WITH INTENT OF THE PLAN.

- SILT FENCES SHALL HAVE SEDIMENT REMOVED WHEN THE DEPTH OF THE SEDIMENT IS EQUAL TO 1/2 TO 1/2 THE HEIGHT OF THE FENCE. FENCES SHALL BE PROPERLY INSTALLED AND RIPPED FENCE OR BROKEN POSTS REPAIRED AS SOON
- ANTI-TRACKING PADS AND GRAVEL CHECK DAMS SHALL BE REPLACED WHEN VOID SPACES ARE FULL OR STRUCTURES ARE BREACHED, AS APPLICABLE.
- TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED AND THE SOIL SURFACE STABILIZED WHEN CONSTRUCTION IS COMPLETE AND THE SOIL SURFACES ARE PERMANENTLY STABILIZED. STRUCTURAL COMPONENTS SHALL BE CLEANED OF ALL SEDIMENT UPON COMPLETION OF CONSTRUCTION.
- THE OWNER IS ASSIGNED THE RESPONSIBILITY FOR IMPLEMENTING THIS EROSION AND SEDIMENT CONTROL PLAN, THIS RESPONSIBILITY INCLUDES INSTALLATION AND MAINTENANCE OF CONTROL MEASURES. INFORMING ALL PARTIES ENGAGED ON THE CONSTRUCTION SITE OF THE REQUIREMENTS AND OBJECTIVES OF THE PLAN. NOTIFYING THE PLANNING AND ZONING COMMISSION OF ANY TRANSFER OF THIS RESPONSIBILITY, AND FOR CONVEYING A COPY OF THE EROSION AND SEDIMENT PLAN IF AND WHEN THE TITLE OF LAND IS TRANSFERRED

### **ROOT PRUNING NOTES**

- 1. ROOT PRUNING SHALL BE DONE WHENEVER THERE WILL BE GRADING, CUTTING OR COMPACTION DISTURBANCE UNDERNEATH THE DRIP LINE OF A TREE. PRIOR TO ANY WORK WITHIN DRIP LINE, CONTRACTORS SHOULD CONTACT LANDSCAPE SERVICES TO COORDINATE WORK. ROOT PRUNING SHALL BE DONE PRIOR TO DISTURBANCE OF THE SITE. NO DISTURBANCE SHALL BE DONE WITHIN A DISTANCE OF 3X THE DIAMETER OF THE TREE, DUE TO STABILITY CONCERNS.
- 2. BEFORE DISTURBANCE, MEET WITH PROJECT ARBORIST ON SITE TO CONFIRM LOCATION OF ROOT PRUNING. ROOT PRUNING SHALL BE CONDUCTED AT AN AGREED UPON LOCATION. THIS LOCATION WILL BE MARKED ON THE GROUND BETWEEN THE DISTURBANCE AND THE TREE, TYPICALLY 6" CLOSER TO THE TREE THAN EDGE THE DISTURBANCE.
- 3. ALL ROOTS 3/4"-1.5" DIAMETERS MUST BE PRUNED. IF 2.5" OR LARGER ROOTS ARE ENCOUNTERED, STOP PRUNING IN THAT AREA AND CONTACT PROJECT ARBORIST. ROOT PRUNING SHALL ONLY BE AS DEEP AS NECESSARY TO ENSURE THE CUTTING OF ALL ROOTS WHICH WOULD BE IMPACTED BY THE DISTURBANCE.
- 4. ROOT PRUNING SHALL BE DONE WITH A SHARP TOOL, IN SUCH A WAY THAT DOES NOT PULL ON THE ROOTS, BUT LEAVES SMOOTH CUTS. IT IS PREFERABLE TO EXPOSE THE ROOTS PRIOR TO ROOT PRUNING. AFTER PRUNING, FILL THE AREA WITH QUALITY TOPSOIL AND WATER UNTIL THOROUGHLY SOAKED.
- 5. ONCE EXPOSED, ROOTS MUST BE COVERED WITHIN 8 HOURS. IF ROOTS WILL BE LEFT EXPOSED FOR LONGER THAN 8 HOURS, THEY MUST BE KEPT MOIST. ONE OPTION IS TO PUT MOIST BURLAP OVER THE EXPOSED ROOTS.
- 6. ROOT PRUNING SHALL BE DONE BY OR UNDER THE SUPERVISION OF A CERTIFIED ARBORIST, AND MEET OR EXCEED ANSI A300 OR APPROVED TREE CARE INDUSTRY

# 7. BEFORE DIGGING

- a) FIRST, CONTACT PROJECT ARBORIST AND ARRANGE A SITE VISIT TO DISCUSS
- i) DURING THE SITE VISIT, CONTRACTOR AND PROJECT ARBORISTS WILL DECIDE WHERE THE ROOT PRUNING TRENCH MUST BE DUG
- ii) THE LOCATION OF THE ROOT PRUNING TRENCH WILL BE MARKED ON THE GROUND
- b) CONTRACTOR WILL PERFORM ROOT PRUNING UNDER THE SUPERVISION OF AN ARBORIST, OR HAVE AN ARBORIST PERFORM THE PRUNING.
- i) A CERTIFIED ARBORIST MUST BE ONSITE TO PERFORM OR SUPERVISE THE ROOT PRUNING c) IF MAJOR ROOTS WILL BE PRUNED, OR A LARGE PERCENTAGE OF THE ROOTS
- WILL BE PRUNED, THE TREE MAY REQUIRE OTHER TYPES OF CARE i) FOR MATURE TREES, NO MORE THAN 30% OF ROOTS MAY BE PRUNED.

# DIGGING PROCESS

- a) THE PRUNING TRENCH SHOULD BE CLEARED IN A WAY THAT EXPOSES THE ROOTS WHILE LEAVING THEM INTACT.
- i) USE HAND TOOLS OR AN AIR KNIFE
- ii) DO NOT USE AN EXCAVATOR, AS THIS WILL PULL ON THE ROOTS AND POSSIBLY DAMAGE THE TRUNK iii) IF A ROOT LARGER THAN 2" IS EXPOSED, LEAVE THIS ROOT INTACT AND
- CONTACT LANDSCAPE SERVICES b) ONCE THE ROOTS ARE EXPOSED, USE A SHARP TOOL TO CLEANLY CUT ALL ROOTS WHICH ARE BETWEEN 1-2" DIAMETER, TO THE DEPTH OF THE
- PROPOSED DISTURBANCE i) APPROPRIATE TOOLS INCLUDE SHARP LOPPING SHEARS, HANDSAWS, A SHARPENED AX, A ROOT PRUNER, A STUMP GRINDER, A RECIPROCATING SAW (SAWSALL) AND ANY OTHER SHARP TOOL WHICH LEAVES A CLEAN CUT
- ii) YOU MAY NOT USE A CHAINSAW OR CHAIN TRENCHER TO MAKE THE FINAL iii) ALL ROOTS SHALL BE LEFT WITH A CLEAN, SMOOTH ENDS AND NO RAGGED EDGES

# 9. POST PRUNING

- a) TREE ROOTS MUST BE KEPT MOIST. IF ROOTS ENDS WILL BE LEFT EXPOSED FOR
- MORE THAN 8 HOURS, COVER THE HOLE WITH MOIST BURLAP.
- b) FILL THE HOLE WITH HIGH QUALITY TOP SOIL, MULCH THE AREA WITH TRIPLE SHREDDED HARDWOOD TO A DEPTH OF 3", AND WATER WELL.

# **EXCAVATION/FILL NOTES:**


- 1. NO PROCESSING OF EARTH OF ANY KIND SHALL BE CONDUCTED ON THE SITE EXCEPT FOR MATERIAL THAT IS EXCAVATED DIRECTLY FROM THE PROJECT SITE FOR USE ON THE PROJECT SITE.
- 2. THERE SHALL BE NO SHARP DECLIVITIES, PITS OR DEPRESSIONS.
- 3. PROPER SURFACE DRAINAGE SHALL BE PROVIDED AND GROUNDWATER SHALL NOT BE POLLUTED.
- 4. AFTER EXCAVATION OR FILLING, THE PREMISES SHALL BE CLEARED OF DEBRIS AND TEMPORARY STRUCTURES WITHIN THE TIME PROVIDED IN THE PERMIT. 5. FILL MATERIAL SHALL NOT INCLUDE ORGANIC (FOR EXAMPLE TREE STUMPS. LEAVES. BRUSH OR
- OTHER MATERIALS THAT DECOMPOSE, ETC.) OR PETROLEUM BASED PRODUCTS OR MATERIALS.
- BASE LOT AREA (SQUARE FEET) X 50% OF THE ALLOWABLE TOTAL COVERAGE PERCENTAGE IN RESPECTIVE ZONE X 10' DIVIDED BY 27 CUBIC FEET =

### 22,921 SF X (0.5 X 25%) X 10 / 27 = 1,061.2 CY


PROPOSED FILL: 100 CY PROPOSED CUT: 0 CY

### TREE PROTECTION NOTES

- 1. ALL TREES WHICH ARE TO REMAIN ON SITE SHALL BE PROTECTED WITH A (4') TALL BRIGHTLY COLORED PLASTIC FENCE, OR SILT FENCE, PLACED AT THE DRIP LINE OF THE TREES.
- 2. A ROOT PROTECTION ZONE WILL BE ESTABLISHED AROUND EACH TREE OR ANY VEGETATION TO BE PRESERVED BASED ON DISCUSSIONS WITH THE NEIGHBOR. THE ROOT PROTECTION ZONE SHALL BE AN AREA DEFINED BY THE RADIUS EXTENDING OUTWARD FROM THE TRUNK OF THE TREE. THE ROOT PROTECTION ZONE WILL BE ESTABLISHED AROUND EACH TREE OR ANY VEGETATION TO BE PRESERVED. THE ROOT PROTECTION ZONE SHALL BE AN AREA DEFINED BY THE RADIUS EXTENDING OUTWARD FROM THE TRUCK OF THE TREE A DISTANCE OF ONE (1) LINEAR FOOT FOR EACH DIAMETER INCH AT BREAST HEIGHT OF THE TREE. FOR EXAMPLE, A 10-INCH DIAMETER TREE WILL HAVE A 10-FOOT RADIUS ROOT PROTECTION ZONE.
- 3. PRIOR TO THE PRE-CONSTRUCTION MEETING, ALL TREE MARKINGS AND PROTECTIVE FENCING SHALL BE INSTALLED BY THE OWNER AND SHALL BE INSPECTED BY THE DEVELOPMENT SERVICES LANDSCAPE ARCHITECT. NO WORK SHALL BEGIN WHERE TREE PROTECTION FENCING HAS NOT BEEN INSTALLED PER THE SITE DEVELOPMENT DOCUMENTS. TREE PROTECTION FENCING SHALL BE INSTALLED, MAINTAINED AND REPAIRED BY THE CONTRACTOR DURING CONSTRUCTION. THE FENCING WILL BE A MINIMUM OF 4 FEET HIGH.
- 4. NO EQUIPMENT SHALL BE CLEANED, OR HARMFUL LIQUIDS DEPOSITED WITHIN THE LIMITS OF THE ROOT ZONE OF TREES WHICH REMAIN ON SITE.
- 5. ROOTS OR BRANCHES IN CONFLICT WITH CONSTRUCTION SHALL BE CUT CLEANLY ACCORDING TO PROPER PRUNING METHODS.
- 6. NO SIGNS, WIRES, OR OTHER ATTACHMENTS SHALL BE ATTACHED TO ANY TREE TO REMAIN ON SITE. 8.5" X 11" SIGN LAMINATED IN -
- 7. VEHICULAR AND CONSTRUCTION EQUIPMENT SHALL NOT PARK OR DRIVE WITHIN THE LIMITS OF THE DRIP LINE. GRADE CHANGES IN EXCESS OF 3 INCHES (CUT OR FILL) SHALL NOT BE ALLOWED WITHIN A ROOT ZONE, UNLESS ADEQUATE TREE PRESERVATION METHODS ARE IN PLACE.
- 8. TRENCHING SHALL BE MINIMIZED WITHIN THE DRIP-LINE OF A TREE. ALL REMOVED TREES SHALL BE CHIPPED AND USED FOR MULCH ON SITE OR HAULED OFF-SITE.
- 9. EXPOSED ROOTS SHALL BE COVERED AT THE END OF THE WORK DAY USING TECHNIQUES SUCH AS COVERING WITH SOIL, MULCH, OR WET BURLAP.
- 10. TREE WHICH ARE DAMAGED OR LOST DUE TO THE CONTRACTOR'S NEGLIGENCE DURING THE CONSTRUCTION PHASE SHALL BE MITIGATED.
- 11. TREES MUST BE MAINTAINED IN GOOD HEALTH THROUGHOUT THE CONSTRUCTION PROCESS. MAINTENANCE MAY INCLUDE WATERING THE ROOT PROTECTION ZONE OR WASHING FOLIAGE.
- 12. ALL TREE MAINTENANCE TECHNIQUES SHALL BE IN CONFORMANCE WITH AMERICAN NATIONAL STANDARDS FOR TREE CARE OPERATIONS, ANSI A300 INDUSTRY IDENTIFIED STANDARDS. IMPROPER OR MALICIOUS PRUNING TECHNIQUES ARE STRICTLY PROHIBITED.







TEST HOLE DATA

TEST HOLE 1

TEST HOLE 2

TEST HOLE 3

TEST HOLE 4

0 - 12"

0 – 11" 11- 40"

SOIL TEST CONDUCTED ON MARCH 14, 2024

ROOTS TO 45"

GREY SANDY LOAM

GRAY SANDY LOAM

GREY SANDY LOAM ROOTS TO 21"

PERCOLATION TEST DATA

10:15

10:25

10:35

10:45

10:55

11:05

11:15

Depth:

10:30

10:40

10:50

11:00

11:10

11:20

Soil Tests Conducted on July 31, 2015

Roots to 39"

Roots to 38"

Topsoil

Red brown fine sandy loam

Red brown fine sandy loam

Red brown fine sandy loam

Olive brown stony fine sandy loam No Mottling, No G.W., No Ledge

24 in.

Depth

10.00

13.50

16.00

17.50

19.50

21.00

22.50

1" in

Depth

11.00

20.00

23.75

26.25

28.50

30.75

33.00

(in.)

36 in.

(in.)

Date:

Presoak:

Interval

00:10

00:10

00:10

00:10

00:10

00:10

Date:

Interval

00:10

00:10

00:10

00:10

00:10

00:10

(min.)

(min.)

Drop

3.50

2.50

1.50

2.00

1.50

1.50

Drop

(in.)

9.00

3.75

2.50

2.25

2.25

2.25

4.44 minutes

6.67 minutes

(in.)

7/31/2015

(min./in.)

2.86

4.00

6.67

5.00

6.67

6.67

11/30/2016

(min./in.)

1.11

2.67

4.00

4.44

4.44

4.44

8:45

Olive brown stony fine sandy loam

No Mottling, No G.W., No Ledge

Olive brown stony fine sandy loam

No Mottling, No G.W., No Ledge

Final Rate:

Wakeman Farm

Test Hole 1 0 - 16"

Test Hole 2

0 - 13"

13 - 38"

38 - 85"

Test Hole 3

0 - 9"

9 - 30"

30 - 92"

Perc Hole

10:12

10:22

10:32

10:42

10:52

11:02

11:12

Final Rate:

Perc Hole P-2

Depth:

1:00 PM

1:10 PM

1:20 PM

1:30 PM

1:40 PM

1:50 PM

2:00 PM

Final Rate:

16 - 39"

Final Rate:

Perc Hole

ROOTS TO 26"

ROOTS TO 45"

ORANGE BROWN SANDY LOAM

ORANGE BROWN SANDY LOAM

RESTRICTIVE LAYER @ 26"

ORANGE BROWN SANDY LOAM

RESTRICTIVE LAYER @ 26"

ORANGE BROWN SANDY LOAM

RESTRICTIVE LAYER @ 36"

3.50

6.50

8.50

10.00

11.00

RESTRICTIVE LAYER @ 30"

MOTTLING @ 30", GROUNDWATER @ 68", NO LEDGE

MOTTLING @ 26", GROUNDWATER @ 64", NO LEDGE

MOTTLING @ 26", GROUNDWATER @ 71", NO LEDGE

MOTTLING @ 36", GROUNDWATER @ 64", NO LEDGE

(in.)

2.50

1.50

1.50

2.00

1.50

1.00

10.00 minutes

Date: 3/14/2024

(min./in.)

4.00

6.67

6.67

5.00

6.67

10.00

Presoak: 2 hr

Interval

(min.)

00:10


00:10

00:10

00:10


00:10

00:10




1. NO PRUNING SHALL BE PERFORMED EXCEPT BY APPROVED ARBORIST 2. NO EQUIPMENT SHALL OPERATE INSIDE THE PROTECTIVE FENCING INCLUDING DURING FENCE INSTALLATION AND

# TREE PROTECTION DETAIL



GENERAL NOTES
CONTACTOR 100HD BY CULTEC, INC. OF BROOKFIELD, CT. STORAGE PROVIDED = 3.84 CF/FT [0.82 M<sup>3</sup>/3] PER DESIGN UNIT. REFER TO CULTEC, INC.'S CURRENT RECOMMENDED INSTALLATION GUIDELINES.

WHEN INSTALLED ACCORDING TO CULTEC'S RECOMMENDED INSTALLATION INSTRUCTIONS.ALL CONTACTOR 100HD HEAVY DUTY UNITS ARE MARKED WITH A COLOR STRIPE FORMED INTO THE PART ALONG THE LENGTH OF THE CHAMBER, ALL CONTACTOR 100 CHAMBERS MUST BE INSTALLED IN ACCORDANCE WITH ALL APPLICABLE LOCAL,



### PERCOLATION TEST DATA Date: 3/14/2024 30 in. Presoak: 2 hr Drop Interval (min.) (min./in.) (in.) 2.00 5.00 5.50 1.50 00:10 REVISED COVERAGE CHART 7.00 1.50 00:10 6.67 8.00 1.00 00:10 10.00 REVISED PER AHD COMMENTS 9.00 1.00 00:10 10.00 REVISED TO SHOW WPLO LINE 10.00 1.00 00:10 10.00 REVISION DATE 1" in 10.00 minutes

HELLO@LANDTECHCONSULT.COM • WWW.LANDTECHCONSULT.COM

WAKEMAN TOWN FARM

SITE/CIVIL • ENVIRONMENTAL • SURVEYING • PLANNING

518 RIVERSIDE AVENUE • WESTPORT, CT 06880 • 203-454-2110

PROJECT LOCATION: 134 CROSS HIGHWAY

PROJECT TITLE:

SITE IMPROVEMENTS FOR A PROPOSED BARN ADDITION

WESTPORT CT

RAWING TITLE:

NOTES AND DETAILS

PROJECT No. 24084-01							
DATE: 6/12/2024	DESIGNED BY:	CHECKED BY: AS					
SCALE:	•	·					

N.T.S.

DESIGN DEVELOPMENT NOT FOR CONSTRUCTION



**C-2.0** 

MAXIMUM ALLOWED COVER ON TOP OF UNIT SHALL BE 12.0' [3.66 m] THE CHAMBER WILL BE DESIGNED TO WITHSTAND TRAFFIC LOADS STATE AND FEDERAL REGULATIONS. CULTEC CONTACTOR 100HD HEAVY DUTY (NON-TRAFFIC APP.) TYPICAL CROSS SECTION

STABILIZATION GEOTEXTILE AS

THE INSTALLATION OF THE SEPTIC SYSTEM SHALL BE UNDER THE SUPERVISION OF A PROFESSIONAL ENGINEER.

HALTED PENDING REVIEW OF THOSE CONDITIONS.

ELEVATIONS SHOWN REFER TO THE INVERT (FLOW LINE) OF THE PROPOSED LEACHING

UTILIZATION OF EXISTING SEPTIC TANK WILL BE BASED UPON THE INTEGRITY OF THE TANK AND BAFFLES DETERMINED PRIOR TO LEACHING SYSTEM CONSTRUCTION.

PROVIDE A 1,000 GALLON, TWO COMPARTMENT SEPTIC TANK MADE OF CONCRETE WITH A MINIMUM 4.000 PSI CONCRETE PER ASTM STANDARDS. SEPTIC TANK ACCESS SHALL BE OUTFITTED WITH 24" DIAMETER RISERS TO FINISHED GRADE WHERE SOIL COVER OVER THE TANK EXCEEDS 12 INCHES. SEAL ALL JOINTS WATERTIGHT. ALL TANK INLET AND OUTLET PIPING SHALL BE SEALED WITH A POLYETHYLENE GASKET, "POLYLOK" OR EQUIVALENT. TANK TO BE WATERTIGHT

ALL RISER ASSEMBLIES UTILIZED SHALL BE EQUIPPED WITH SECONDARY SAFETY LIDS OR DEVICES EVEN IF THE RISER COVER WEIGHS MORE THAN 59 LBS. SECONDARY SAFETY DEVICES SHALL BE IN ACCORDANCE WITH THE STATE OF CONNECTICUT PUBLIC HEALTH CODE. LATEST REVISION

SEPTIC TANK BAFFLES SHALL CONFORM TO TECHNICAL STANDARDS OF THE PUBLIC HEALTH

10. SEPTIC TANK SHALL HAVE AN APPROVED NON-BYPASS EFFLUENT FILTER AT THE OUTLET.

ALL PIPING BETWEEN BARN AND SEPTIC TANK SHALL BE FOUR INCHES IN DIAMETER WITH A MINIMUM SLOPE OF 1/2" PER FOOT OR SIX INCHES IN DIAMETER WITH A MINIMUM SLOPE OF 1/3" PER FOOT. PIPE SHALL BE LAID WITH TIGHT JOINTS AND IN A STRAIGHT LINE WITH UNIFORM GRADES. ACCESSIBLE MANHOLES OR SURFACE CLEANOUTS SHALL BE PROVIDED AT ONE OR MORE CUMULATIVE CHANGES OF DIRECTION EXCEEDING 45 DEGREES OR WHERE BUILDING SEWER EXCEEDS 75 FEET IN LENGTH. MATERIALS TO BE ALLOWED BY TECHNICAL

ALL PIPE USED BETWEEN SEPTIC TANK AND LEACHING AREA SHALL BE 4" SDR-35 PVC PIPE WITH WATERTIGHT JOINTS OR EQUIVALENT ALLOWED BY TECHNICAL STANDARDS. PIPE SHALL BE SET ON A MINIMUM SLOPE OF 1/8" PER FOOT.

DISTRIBUTION BOXES ARE TO BE SET ON A STABLE FOOTING OF 12" MINIMUM DEPTH OF 1" CRUSHED STONE.

ALL FILTER FABRIC SHALL BE 1.5 OZ./YD. (ASTM D-5261), PERMEABILITY OF 1.0/SEC. (AS TM D-4491) AND A TRAPEZOID TEAR OF 15 LBS. (ASTM D-4533) OR EQUIVALENT.

NO FOOTING DRAINS OR OTHER GROUNDWATER DRAINS SHALL BE INSTALLED WITHIN 25' OF PROPOSED SEPTIC SYSTEM OR WITHIN 50 FEET OF SEPTIC SYSTEM IF DRAIN IS DOWN

PRIOR TO CONSTRUCTION ACTIVITIES THE LEACHING SYSTEM AREAS SHALL BE ROPED OFF OR OTHERWISE DELINEATED SO AS TO KEEP CONSTRUCTION TRAFFIC OFF THE SEPTIC

STRIP AND STOCKPILE TOPSOIL AND REMOVE BOULDERS PRIOR TO PLACING FILL. ALL TOPSOIL MUST BE REMOVED IN FILL SYSTEMS.

GRAVEL FILL TO BE DUMPED AT THE EDGE OF PREPARED LEACHING AREA AND PUSHED ONTO HARROWED SURFACE WITH TRACK MACHINE IN 12" (MAX) LIFTS. GRAVEL TO BE COMPACTED TO 90-95% STANDARDS PROCTOR DENSITY - ASTM D-698. THE ENGINEER OF RECORD AND THE HEALTH DEPARTMENT MUST APPROVE THE SELECT GRAVEL PRIOR TO ITS PLACEMENT

SELECT FILL SHALL BE COMPRISED OF CLEAN SAND, OR SAND AND GRAVEL, FREE FROM ORGANIC MATTER AND FOREIGN SUBSTANCES. SELECT FILL SHALL MEET THE FOLLOWING REQUIREMENTS:

A. THE SELECT FILL SHALL NOT CONTAIN ANY MATERIAL LARGER THAN THE 3 INCH SIEVE. B. UP TO 45% OF THE DRY WEIGHT OF THE REPRESENTATIVE SAMPLE MAY BE RETAINED ON THE #4 SIEVE.

THE MATERIAL THAT PASSES THE #4 SIEVE IS TO BE REWEIGHED AND A SECOND SIEVE ANALYSIS COMPLETED.

THE REMAINING SAMPLE SHALL MEET THE FOLLOWING GRADATION CRITERIA.

SIEVE SIZE	PERCENT PASSING		
SIEVE SIEE	WET SIEVE	DRY SIEVE	
#4	100	100	
#10	70-100	70-100	
#40	10-50*	10-75	
#100	0-20	0-5	
#200	0-5	0-2.5	

\*PERCENT PASSING THE #40 SIEVE CAN BE INCREASED TO NO GREATER THAN 75% IF THE PERCENT PASSING THE #100 SIEVE DOES NOT EXCEED 10% AND THE #200 SIEVE DOES NOT EXCEED 5%.

NON-SELECT FILL SHALL BE A CLEAN LOAM OR BETTER FREE OF ORGANIC MATTER.

THIS SYSTEM IS NOT DESIGNED FOR BACKWASH FROM A WATER SOFTENING SYSTEM OR THE OUTFLOW FROM A GARBAGE DISPOSAL OR TUB (BATHTUB, WHIRLPOOL, JACUZZI, ETC.) IN EXCESS OF 100 GALLONS.

MEASUREMENTS FOR AS-BUILT DRAWING TO BE COMPLETED BY PROFESSIONAL ENGINEER PRIOR TO BACKFILLING.

23. FINAL GRADING TO BE COMPLETED IMMEDIATELY AFTER INSPECTION AND COMPLETION OF MEASUREMENTS FOR AS-BUILT DRAWING.

24. THERE ARE NO WELLS WITHIN 75' OF PROPOSED SEPTIC SYSTEM.

NDTECH

25. THIS DESIGN CONFORMS TO APPLICABLE CODES AND ACCEPTED PRACTICE. NO OTHER WARRANTY IS EXPRESSED OR IMPLIED.

LAND-TECH CONSULTANTS, INC., ASSUMES NO RESPONSIBILITY FOR SEPTIC SYSTEM SITE PREPARATION, LOCATION OR INVERT ELEVATIONS IN COMPLIANCE WITH THE APPROVED PLAN, UNLESS IT SUPERVISES EACH PHASE OF SYSTEM INSTALLATION.

BASED ON A VISUAL INSPECTION OF NEIGHBORING PROPERTIES AND A REVIEW OF AVAILABLE RECORDS, NO PART OF THE PROPOSED SEPTIC SYSTEM IS WITHIN THE REQUIRED SEPARATION DISTANCE FROM A WATER SUPPLY WELL, OR CLOSED LOOP GEOTHERMAL SYSTEM BOREHOLE/TRENCH AS DEFINED IN TABLE 1 OF THE "TECHNICAL STANDARDS FOR SUBSURFACE SEWAGE DISPOSAL SYSTEMS", LATEST REVISION.

**SEPTIC SYSTEM DESIGN CALCULATIONS - BARN** 

20 PERSON OF DAY CAMP USE @15 GPD / PERSON (ACTIVITY ROOM) 646.1 SF X 0.1 GPD/SF + 20 PERSON \* 15 GPD/ PERSON = 365 GPD PERCOLATION RATE = 1 INCH 0 - 10.0 MINUTES USED FOR DESIGN (OBSERVED PERCOLATION RATE OF 1" IN LESS THAN 10.0 MINUTES) SQUARE FEET OF LEACHING AREA REQUIRED = 365 DESIGN FLOW / 1.5 APPLICATION RATE = 243.3 SF (TABLE 8)

PROPOSED SEPTIC SYSTEM LEACHING FIELD 45 LF OF 12" CONCRETE LEACHING GALLERIES 45 LF X 5.9 SF/LF = 265.5 SF OF LEACHING AREA PROVIDED 1000 GAL. SEPTIC TANK PROVIDED

45 LF OF 12" CONCRETE LEACHING GALLERIES 45 LF X 5.9 SF/LF = 265.5 SF OF LEACHING AREA PROVIDED MLSS CALCULATION - BARN

HYDRAULIC FACTOR (HF) HYDRAULIC GRADIENT AT BOTH ENDS OF SYSTEM (204.7 - 202.0) / 66 = 4.1%; (204.4 - 202.5) / 66 = 2.9%AVG. HYDRAULIC GRADIENT = (4.1 + 2.9) / 2 = 3.5% HYDRAULIC GRADIENT = 3.1-4%

AVERAGE DEPTH OF TEST HOLES WITHIN THE SYSTEM: DTH-1 = 30", DTH-2= 26" (30 + 26) / 2 = 28" DEPTH OF DOWNGRADIENT TEST HOLE = DTH-3 = 26" AVERAGE DEPTH OF RESTRICTIVE LAYER = (28 + 26) / 2 = 27"

FLOW FACTOR (FF): DESIGN FLOW 365 GPD

PERCOLATION FACTOR (PF): PERCOLATION RATE = 1" IN 10.1 - 20.0 MINUTES

MLSS = 34 X 1.22 X 1.0 MLSS = 41.5 FEET

PRIMARY LEACHING SYSTEM SPREAD = 45 FEET

**INVERT ELEVATIONS- BARN** BUILDING SEWER AT FOUNDATION = 203.7 MIN.

SEPTIC TANK INLET = 203.33

PUMP CHAMBER

INLET 202.90

**DISTRIBUTION BOX** INLET = 204.05

LEACHING SYSTEM INVERT = 203.95

## FLOW CALCULATION - EXISTING RESIDENCE

FLOW RATE TABLE						
Use	Occupancy	Comment	Design Flow*	Projected Sewage Flow (gpd)	Application Rate** (gpd/sf)	ELA
4 Bedroom Dwelling	4 family members		TABLE 6	577.5	NA	900.0
Commercial Kitchen	10	3-4/month,	5 gpd / meal served	50	0.8	62.5
Day Care- Mornings - 1 to 4 yr olds	10		10 gpd / pupil	100	1.5	66.7
Day Care- After school - 8 to 12 yr olds	21	No lunch prep	10 gpd / pupil	210	1.5	140.0
Summer Day Camp	40	6 weeks No food preparation	15 gpd / person	600	1.5	400.0
		Total	1,538		1569.2	

└ 3,5" DIA. INLETS

\* Table 4 - Technical Standards \*\* Tables 7 & 8- Technical Standards (Assumes > 1"/10 min\_percolation rate)

SEPTIC SYSTEM DESIGN CALCULATIONS - EXISTING RESIDENCE

2,000 GAL. SEPTIC TANK PROVIDED (EXISTING)

PROPOSED SEPTIC SYSTEM LEACHING FIELD 90 LF OF MANTIS DW-100 (45 LF EXISTING TO REMAIN, 45 LF PROPOSED) 90 LF X 20.0 SF/LF = 1,800 SF OF LEACHING AREA PROVIDED


MLSS CALCULATION - EXISTING RESIDENCE

RESTRICTIVE LAYER > 60 MLSS DOES NOT APPLY INVERT ELEVATIONS- EXISTING RESIDENCE

OUTLET = 202.0


EXISTING LEACHING SYSTEM INVERT = 201.90 (TO REMAIN) EXISTING LEACHING SYSTEM BOTTOM = 200.90 (TO REMAIN)

PROPOSED LEACHING SYSTEM INVERT= 201.10 PROPOSED LEACHING SYSTEM BOTTOM = 200.10




SECTION VIEW


# DISTRIBUTION BOX WITH BAFFLE




HIGH LEVEL OVERFLOW (HLO) DISTRIBUTION BOX


EXTEND MANHOLES TO GRADE -LOCATE OVER INLET AND OUTLET IF GREATER THAN 24" COVER OVER SEPTIC TANK - APPROVED OUTI FT - INLET BAFFLE FILTER OUTLET BAFFLE 2/3 LENGTH — — 1/3 LENGTH — LENGTH NOT GREATER THAN FOUR TIMES WIDTH OR DEPTH














MANTIS VENTING DETAIL - "CANDY CANE" TYPICAL SECTION



1,000 GALLON PUMP CHAMBE



12"x48" PRECAST CONCRETE GALLERY TYPICAL CROSS SECTION



REVISED COVERAGE CHART 8/30/2024 REVISED PER AHD COMMENTS REVISED TO SHOW WPLO LINE 7/8/2024

SITE/CIVIL • ENVIRONMENTAL • SURVEYING • PLANNING 518 RIVERSIDE AVENUE • WESTPORT, CT 06880 • 203-454-2110 HELLO@LANDTECHCONSULT.COM • WWW.LANDTECHCONSULT.COM

WAKEMAN TOWN FARM

134 CROSS HIGHWAY WESTPORT CT

SITE IMPROVEMENTS FOR A PROPOSED BARN ADDITION


AWING TITLE:

NOTES AND DETAILS

24084-01 CHECKED BY: DESIGNED BY: 6/12/2024 RW

N.T.S.

DESIGN DEVELOPMENT NOT FOR CONSTRUCTION



**C-3.0**